

SHEARWALL SCHEDULE	
MARK	PLYWOOD AND NAILING
1	3/8" APA RATED PLYWOOD OR OSB w/ 8d @ 6" O.C. EDGES & 8d @ 12" O.C. FIELD
2	(N) 2x6 DF#2 AT 16" O.C. IN-FILL FRAMING w/ 3/8" APA RATED PLYWOOD OR OSB w/ 8d @ 6" O.C. EDGES & 8d @ 12" O.C. FIELD
	SILL BOLTING - SEE DETAIL D1

SHEARWALL NOTES

- SEE DETAILS D2, D3, & D4 FOR TYPICAL SHEARWALL CONSTRUCTION.
- ALL NAILS SHALL BE COMMON WIRE NAILS.
- PROVIDE PLYWOOD EDGE NAILS FULL HEIGHT OF KING STUDS, TYPICAL AT WALL OPENINGS AND ALL STUDS WITH HOLDDOWNS.
- PRE-DRILL ALL HOLES WHERE WOOD TENDS TO SPLIT.


LEGEND

- FOOTING. SEE SCHEDULE THIS SHEET.
- SHEARWALL. SEE SCHEDULE THIS SHEET.
- COLUMN. SEE SCHEDULE THIS SHEET.
- HD2A

SIMPSON HOLDDOWN. SEE DETAIL D6 FOR (N) HOLDDOWN AT (E) FOOTING AND D7 FOR (N) HOLDDOWN AT (N) FOOTING.


COLUMN AND POST SCHEDULE	
MARK	SIZE
1	3" DIA. STD. PIPE COLUMN
2	6x6 DF#1 POST
3	
4	

FOOTING SCHEDULE		
MARK	FOOTING. SIZE	REINFORCING
1	1'-0" WIDE x 1'-6" DEEP CONTIN. FOOTING INTO UNDISTURBED SOIL	#4 CONTIN. TOP & BTM.
2	1'-6" WIDE x 1'-6" DEEP CONTIN. FOOTING INTO UNDISTURBED SOIL	2-#4 CONTIN. TOP & BTM.
3	2'-0" SQUARE x 1'-6" DEEP PAD FOOTING INTO UNDISTURBED SOIL	(3) #4 EACH WAY AT BTM.
4	2'-6" SQUARE x 1'-6" DEEP PAD FOOTING INTO UNDISTURBED SOIL	(4) #4 EACH WAY AT BTM.
5	2'-9" SQUARE x 1'-6" DEEP PAD FOOTING INTO UNDISTURBED SOIL	(4) #4 EACH WAY AT BTM.
6	BUMP FOOTING OUT TO FACE OF PILASTER FRAMING PER ARCH. PLANS TO CREATE PAD FOOTING BELOW ARCHITECTURAL PILASTER.	



FOUNDATION PLAN

REV	DATE/DESC



THESE PLANS PREPARED UNDER THE DIRECT SUPERVISION OF:

[Signature]
BRANDON O. SALGADO
RCE 71320

1129 Union Avenue
Bakersfield, Ca

Foundation Plan

Afinar
civil engineers/surveyors/planners/construction managers

2005 Eye Street, Suite 3
Bakersfield, CA 93301

phone(661)716-7443
fax(661)716-7444
www.afinar.net

DATE:	03-26-09
SCALE:	AS NOTED
DRAWN:	AA/LJF
JOB NO:	0734

S-20