

NOTE:

INSTALLATION OF SOIL AND DRAIN PIPES IN FOOD HANDLING ESTABLISHMENTS MUST COMPLY WITH SECTION 318.0 CPC.

BUILDING DRAIN AND VENT PIPING MATERIALS SHALL COMPLY WITH SECTIONS 701.0 AND 903.0 OF THE CALIFORNIA PLUMBING CODE.

ALL SANITARY SYSTEM MATERIALS SHALL BE LISTED BY AN APPROVED LISTING AGENCY.

FLOOR DRAINS OR SIMILAR TRAPS DIRECTLY CONNECTED TO THE DRAINAGE SYSTEM AND SUBJECT TO INFREQUENT USE SHALL BE PROVIDED WITH AN APPROVED AUTOMATIC MEANS OF MAINTAINING THEIR WATER SEALS.

PERMANENT VACUUM BREAKERS SHALL BE INCLUDED WITH ALL HOSE BIBS.

EACH FAUCET SHALL NOT EXCEED A WATER FLOW OF 2.2 GPM.

CROSS CONNECTION PROTECTION SHALL BE PROVIDED AT ALL POTABLE WATER SUPPLIED APPLIANCES AND EQUIPMENT (OTHER THAN THOSE LISTED IN INFORMATION BULLETIN 103).

PROVIDE EXPANSION TANK OR OTHER APPROVED METHOD OF RELIEVING PRESSURE PER SECTION 608.3 CPC.

ROUTING AND TERMINATION OF FLUE FOR WATER HEATER SHALL COMPLY WITH CH. 5, CPC 2007.

WATER HEATER SHALL BE ANCHORED AND STRAPPED TO RESIST HORIZONTAL DISPLACEMENT DUE TO EARTHQUAKE MOTION PER SECTION 508.2 CPC.

ALL POTABLE WATER PLUMBING PIPING, FITTINGS, DEVICES, FIXTURES, SOLDER OR FLUX SHALL BE "LEAD FREE" IN COMPLIANCE WITH CALIFORNIA HEALTH AND SAFETY CODE SECTION 116875 (AB 1953, JANUARY 1,2010)

ALL PIPING, FITTINGS, DEVICES, FIXTURES, SOLDER OR FLUX SHALL BE CERTIFIED BY AN INDEPENDENT AMERICAN NATIONAL STANDARD INSTITUTE (ANSI) ACCREDITED AGENCY AS BEING IN COMPLIANCE WITH REQUIREMENT CPC 301.0

ANY PROPOSED CARBONATED BEVERAGE DISPENSER TO BEAR LABEL OF AN APPROVED TESTING AGENCY CERTIFYING AND ATTESTING THAT SUCH EQUIPMENT HAS BEEN TESTED AND INSPECTED, AND MEETS THE REQUIREMENTS OF APPROVED APPLICABLE STANDARD.

INDIRECT WASTE DRAIN LINE FROM CARBONATOR BACKFLOW PREVENTER TO DISCHARGE WITH REQUIRED AIR GAP ABOVE APPROVED OPEN RECEPTOR.


WALK IN COOLER AND FREEZER TO BE FITTED WITH SELF
EVAPORATING DRIP PAN FROM MANUFACTURER.

3 COMPARTMENT SINK AND PREP SINK TO DRAIN INDIRECTLY
TO FLOOR SINK WITH 1" AIR GAP.

ALL PIPING TO BE PVC.



SCALE: 1/4" = 1'-0"



NO.	DATE

SUBWAY
SUITE B
89960 FLETCHER PKWY
LA MESA, CA 91942

THESE PLANS ARE NOT
FOR CONSTRUCTION
UNLESS A "WET STAMP &
SIGNATURE" FROM BOTH
THE ENGINEER OF RECORD
AND A APPROVAL STAMP
WITH A "WET STAMP &
SIGNATURE" FROM THE
LOCAL GOVERNING
AGENCY ARE PRESENT.

DWG. BY	J.P.
CHK'D BY	
DATE	7/30/2010
JOB NO.	6190
FILE NO.	619022

EXP. 12/31/10

SHEET

P-3

PRINTED: 10/8/2010