







NOTE: CAN NOT BE USED ABOVE
BANQUETTE WALL BENCH SEATING.



		DRYWALL	UNBONDED	WOOD PARTICLE BOARD
AX	SUNGLO GITYSCAPE MURAL			
	FLAME SPREAD INDEX	10		
	FUEL CONTRIBUTED VALUE	0		
	SMOKE DEVELOPED VALUE	5		
	SUNGLO TUSCAN			
	STUCCO WALL COVERING			
	FLAME SPREAD INDEX	15		
	FUEL CONTRIBUTED VALUE	5		
	SMOKE DEVELOPED VALUE	10		
	SUNGLO BUTTERNUT BRICK			
CAR	WALL COVERING			
	FLAME SPREAD INDEX	15		
	FUEL CONTRIBUTED VALUE	5		
	SMOKE DEVELOPED VALUE	20		
	SUNGLO QUENTIN			
	WALL COVERING			
	FLAME SPREAD INDEX	10		
	FUEL CONTRIBUTED VALUE	0		
	SMOKE DEVELOPED VALUE	5		
	SUNGLO RED WALL COVERING			
LY	FLAME SPREAD INDEX	15		
	FUEL CONTRIBUTED VALUE	0		
	SMOKE DEVELOPED VALUE	20		
	WILSONART LAMINATE (G.P.)			
	FLAME SPREAD INDEX	55		
	FUEL CONTRIBUTED VALUE	0		
	SMOKE DEVELOPED VALUE	30		
	MARLITE FIBERGLASS			
	REINFORCED PANELS			
	FLAME SPREAD INDEX	200		
MIN	FUEL CONTRIBUTED VALUE	0		
	SMOKE DEVELOPED VALUE	450		
	VACUIFORM MOSAIC TILE			



FRONT SERVICE COUNTER ELEVATION (TYPICAL)
(SEE GENERAL NOTES 1, 2, 4 & 6)

SHEET #:

PRINTED: 11/8/2010