


**1 FURNITURE AND EQUIPMENT PLAN**  
SCALE: 1/4" = 1'



**2 REFLECTED CEILING AND LIGHTING PLAN**  
SCALE: 1/4" = 1'

## FURNITURE AND EQUIPMENT LEGEND

#	ITEM	MANUFACTURER	ORDERED FROM	QTY	DESCRIPTION
<b>CUSTOMER AREA</b>					
4A	30" X 42" TABLE	PLYMOLD	DAI	1	30" HIGH W/ (1) VERTICAL TABLE LEG AT EACH OF THE 4 CORNERS. FINT HILL PEAR LAMINATE WITH BLACK DURA EDGE.
4B	20" X 24" TABLE	PLYMOLD	DAI	6	30" HIGH W/ FREESTANDING 20" X 24" CROSS BASE. FINT HILL PEAR LAMINATE WITH BLACK DURA EDGE.
5A	30" ROUND BAR HEIGHT TABLE	PLYMOLD	DAI	4	42" HIGH W/ FREESTANDING 30" X 30" CROSS BASE. FINT HILL PEAR LAMINATE WITH BLACK DURA EDGE.
6A	CHAIR	PLYMOLD	DAI	16	GUEST CHAIR W/ UPHOLSTERED SEAT OR DURA-SEAT TO BE ORDERED IN THE FOLLOWING COLORS: CROCODUS, SPICE AND SLATE. FRAME COLOR IS BLACK WRINKLE.
6B	BAR HEIGHT STOOL	PLYMOLD	DAI	12	GUEST STOOL W/ UPHOLSTERED SEAT OR DURA-SEAT TO BE ORDERED IN THE FOLLOWING COLORS: CROCODUS, SPICE AND SLATE. FRAME COLOR IS BLACK WRINKLE.
8A	TRASH RECEPTACLE	PLYMOLD	DAI	1	(X) 25" X 25" SINGLE HOLE TRASH UNIT OR (X) 18 5/8" X 18 5/8" SPACE SAVER TRASH UNIT. BLACK DURA EDGE TRASH RECEPTACLE W/ FINT HILL PEAR LAMINATE FINISH.
9A	SODA FOUNTAIN	CORNELIUS	DAI	1	DEDICATED 115V, 20 AMP DUPLEX OUTLET (NEMA 5-20R) W/IN 3 FEET, 3 INCH OR LARGER FLOOR DRAIN W/IN 3 FEET (EQUIPMENT INSTALLED BY CODE).
9B	TEA/COFFEE BREWER	BUNN-D-MATIC CORP.	DAI	1	DEDICATED 120V, 15 AMP DUPLEX OUTLET (NEMA 5-15P) W/IN 3 FEET, PLUMBING 20-90 PSI, MODEL SUPPLIED WITH 1/4" MALE FLARE FITTING, MIN. 1/2" GPM WATER FLOW.
10	BEVERAGE DISTRIBUTION CENTER	DUKE MANUFACTURING	DAI	1	(X) 36" X 14" BEVERAGE PLACEMENT (X) 36" X 14" X 72" (X) 36" X 14" X 72" (X) 36" X 14" X 72". STAINLESS STEEL TOP. FINT HILL PEAR LAMINATE FINISH. INSTALLED BY G.C.
11	SUBWAY OPEN VIDEO SIGN MOUNTED	SEE MANUFACTURER FOR SPECS	120V, INSTALLED BY G.C.		
13A	WALL ART-VERTICAL	SUNGLO FABRICS	DAI	6	23" X 50" WALL HUNG PRINT(S) ON STYRENE-FACED FOAMBOARD FRAMED IN BLACK METAL. MOUNTING HARDWARE INCLUDED. EIGHT DIFFERENT PRINT IMAGES AVAILABLE.
13B	WALL ART-SQUARE	SUNGLO FABRICS	DAI	2	26" X 26" WALL HUNG PRINT(S) COLOR PHOTOS DOUBLE MATTED IN A BLACK WOODEN FRAME. MOUNTING HARDWARE INCLUDED. EIGHT DIFFERENT PRINT IMAGES AVAILABLE.
14	CHIP RACK	FRITO-LAY	DAI	1	(X) 24" X 16 3/8" X 68" X 54" (X) 33 1/4" X 16 3/8" X 68" FLOOR RACKS. / (X) 24" X 12" X 12" X 22" COUNTER TOP RACKS. THROUGH LOCAL DIST.
15	DISPLAY REFRIGERATOR	TRUE	DAI	1	(X) 11 DOOR FLOOR MODEL. / (X) 26 DOOR FLOOR MODEL. DEDICATED 115V, 15 AMP DUPLEX OUTLET (NEMA 5-15P) W/IN 6 FEET.
16	WALL PLANT	GRACE DESIGNS	DAI	1	WALL HUNG SILK PLANT. MOUNTING BRACKET TO BE HUNG 15" BELOW THE TOP OF THE UPPER DECORATIVE HOLDING REFER TO TUSCANY II BACK-UP SHEET #1.
17	INTERIOR DOOR	LOCAL	G.C.	1	SOLID CORE MOUNTED DOOR GLASS OR PANEL OR OTHER STAINLESS STEEL OR POLYURETHANE W/ MINIMUM FAST DRYING SATIN METAL FRAME PAINT SERVING WILLIAMS #5626 COPPER MOUNTED LEVER HANDLE INSTALLED BY G.C.
18	GUIDANCE SYSTEM	LAVI INDUSTRIES	DAI	4	BELTRAC SYSTEM. BLACK PDST WITH RETRACTABLE HORIZONTAL NYLON BELT.
<b>SERVICE AREA</b>					
19	FRONT COUNTER	DUKE MANUFACTURING	DAI	1	TOTAL LENGTH 17'-2". (X) 14" X 30" X 74" (X) 24" X 30" X 74" (X) 24" X 48" X 74" (X) 24" X 48" X 74" (X) 24" X 48" X 74". DESK SURFACE, OVERHEAD SHELVES AND LOCKABLE CAGE. SUPER ERECTA BRITE. INSTALLED BY G.C. ULS APPROVED. ELECTRICAL CONNECTIONS AND WIRING TO LOCAL AND STATE CODE REQUIREMENTS AS DETERMINED BY G.C. OR ELECTRICIAN.
21	COOKIE DISPLAY CASE	AMERICAN DISPLAYS IN PLASTICS, INC.	DAI	1	DISPLAY CASE ON TOP OF SUB-WRAP AND NAPKIN RISER. MADE OF CLEAR ACRYLIC.
23	SAFE	C.S.S./TIDEL	DAI	1	(X) TIME LOCK (X) QUICK DROP (X) 72" TALL. INSTALLED BY G.C. IN SERVICE AREA.
24	POUR-SP DISP. 2000 P.D.S.	HOBB STORE/BLAUBERG/PC-HB	DAI	1	PC BASED POUR-SP SYSTEM. REQUIRES DEDICATED POWER SOURCE WITH ISOLATED GROUND TO BREAKER.
25	MICROWAVE	AMANA/SHARP	DAI	1	15-20R OUTLET REQUIRED. 1200 WATT, 120V/60HZ/1PH, 20 AMP CIRCUIT. DEDICATED CIRCUIT REQUIRED.
27	BREAD OVEN	DUKE/NU-VU	DAI	1	(X) DUKE (X) NU-VU. DEDICATED CIRCUIT REQUIRED. DIRECT WIRED. INSTALLED BY G.C. 1/4" WATERLINE IS REQUIRED.
28A	COMBI BREAD CABINET	LOCKWOOD	DAI	1	(X) 36" X 14" COMBINATION CABINET. INTEGRATED OPEN AIR COOLING RACK ABOVE WITH ENCLOSED CABINET BELOW. INSTALLED BY G.C.
28B	FRONTLINE REFRIG. BREAD CABINET	LOCKWOOD	DAI	1	FINT HILL PEAR LAMINATE FINISH ON BACK AND SIDES TO 36" HEIGHT. GLASS BACK AND SIDES TO TOP. INSTALLED BY G.C. NSF APPROVED.
29	MENU BOARD	LYGES X TRANSLITE SONOMA	DAI	1	MENU BOARD (X) 42" X 24" (X) 42" X 24" (X) 42" X 24" (X) 42" X 24" (X) 42" X 24". LIGHT FIXTURES (X) 2" X 2" (X) 2" X 2" (X) 2" X 2" (X) 2" X 2" (X) 2" X 2". SINGLE OUTLET REQUIRED. INSTALLED BY G.C.
30	COUNTER ENTRANCE	PLYMOLD/DUKE MFG.	DAI	1	SELF-CLOSING, PREFRAMED & PREFINISHED OR SEE BACK-UP SHEETS FOR CONSTRUCTION SPECS. FINT HILL PEAR LAMINATE FINISH. INSTALLED BY G.C.
31	BACK COUNTER W/ HAND SINK	DUKE MANUFACTURING	DAI	1	(X) 36" X 14" X CENTER HAND SINK. (X) 24" X 36" X 148" (X) 36" X 148" X 72" LENGTH. STAINLESS STEEL TOP. FINT HILL PEAR LAMINATE FINISH. INSTALLED BY G.C.
32	BACK COUNTER	DUKE MANUFACTURING	DAI	2	(X) 24" X 36" X 148" (X) 36" X 148" X 72" LENGTH. STAINLESS STEEL TOP. FINT HILL PEAR LAMINATE FINISH. INSTALLED BY G.C.
33	REFRIGERATED BACK COUNTER	DUKE MANUFACTURING	DAI	1	(X) 24" X 36" X 148" X 72" LENGTH. BACK COUNTER WITH UNDER-COUNTER REFRIGERATOR. STAINLESS STEEL TOP. FINT HILL PEAR LAMINATE FINISH. INSTALLED BY G.C.
34	RAPID COOK OVEN	TURBOCHEF/HEIRY-CHEF	DAI	1	(X) TURBOCHEF (X) HEIRY-CHEF. MICROVAPE/CONVECTION OVEN. REFER TO TUSCANY II BACK-UP SHEET #4 FOR FURTHER SPECIFICATIONS.
<b>BACKROOM AREA</b>					
35	TRAINING STATION	INTER METRO	DAI	1	(X) 24" X 30" X 74" (X) 24" X 30" X 74" (X) 24" X 48" X 74" (X) 24" X 48" X 74" (X) 24" X 48" X 74". DESK SURFACE, OVERHEAD SHELVES AND LOCKABLE CAGE. SUPER ERECTA BRITE. INSTALLED BY G.C. ULS APPROVED. ELECTRICAL CONNECTIONS AND WIRING TO LOCAL AND STATE CODE REQUIREMENTS AS DETERMINED BY G.C. OR ELECTRICIAN.
36	SINK	DUKE MANUFACTURING	DAI	1	(X) 24" X 30" X 74" (X) 24" X 30" X 74" (X) 24" X 48" X 74" (X) 24" X 48" X 74" (X) 24" X 48" X 74". DESK SURFACE, OVERHEAD SHELVES AND LOCKABLE CAGE. SUPER ERECTA BRITE. INSTALLED BY G.C. ULS APPROVED.
37	WIP SINK	LOCALLY SOURCED	G.C.		FLOOR LEVEL SINK. 2' X 2' (PREFERRED). ACQUIRE LOCALLY. INSTALLED BY G.C.
38	HOT WATER TANK	LOCALLY SOURCED	G.C.		ACQUIRE LOCALLY. INSTALLED BY G.C.
39	S.S. WORKTABLE	DUKE MANUFACTURING	DAI	1	(X) 24" X 36" X 148" (X) 36" X 148" X 72" LENGTH. STAINLESS STEEL TOP. FINT HILL PEAR LAMINATE FINISH. INSTALLED BY G.C.
40	WALL SHELF	INTER METRO	DAI	4	SUPER ERECTA BRITE. EPOXY COATED. WALL MOUNTED SHELVES. AVAILABLE IN VARIOUS SIZES. INSTALLED BY G.C.
41	VEGETABLE SINK	DUKE MANUFACTURING	DAI	1	(X) 24" X 30" X 74" (X) 24" X 30" X 74" (X) 24" X 48" X 74" (X) 24" X 48" X 74" (X) 24" X 48" X 74". DESK SURFACE, OVERHEAD SHELVES AND LOCKABLE CAGE. SUPER ERECTA BRITE. INSTALLED BY G.C. ULS APPROVED.
43	CLEANING PRODUCT RACK	SSS	DAI	1	DISPENSING STATION FOR CLEANING PRODUCTS.
45	NEMCO EASY-SLICER	NEMCO, INC.	DAI	1	MANUAL SLICER MOUNTED ON STAINLESS STEEL TABLE TOP. NSF APPROVED.
46	RETARDER CABINET	LOCKWOOD	DAI	1	(X) 36" X 14" X CENTER HAND SINK. (X) 24" X 36" X 148" (X) 36" X 148" X 72" LENGTH. STAINLESS STEEL TOP. FINT HILL PEAR LAMINATE FINISH. INSTALLED BY G.C.
47	REFRIGERATOR	NORLAK	DAI	1	(X) 24" X 36" X 148" (X) 36" X 148" X 72" LENGTH. STAINLESS STEEL TOP. FINT HILL PEAR LAMINATE FINISH. INSTALLED BY G.C. NSF APPROVED.
48	REFRIGERATOR	NORLAK	DAI	1	(X) 24" X 36" X 148" (X) 36" X 148" X 72" LENGTH. STAINLESS STEEL TOP. FINT HILL PEAR LAMINATE FINISH. INSTALLED BY G.C. NSF APPROVED.
49	STORAGE UNITS	INTER METRO	DAI	5	(X) 24" X 36" X 148" (X) 36" X 148" X 72" LENGTH. STAINLESS STEEL TOP. FINT HILL PEAR LAMINATE FINISH. INSTALLED BY G.C.
50	SODA STORAGE	COKE	DAI	1	DEDICATED 115V, 20 AMP DUPLEX OUTLET (NEMA 5-20R) W/IN 3 FEET OF BID RACK. 36 INCHES HIGH/WATER 1/2 INCH BALL VALVE SHUTOFF W/IN 3 FEET OF BID RACK. 36 INCHES HIGH EQUIPMENT INSTALLED BY CODE.
51	STERED SYSTEM	SUBWAY/RADIO/LOCAL	DAI/LOCAL	1	RECEIVER AND AMPLIFIER WITH THREE SPEAKERS MOUNTED AND PROFESSIONALLY WIRED IN CEILING. OPTIONAL SUBWAY'S RADIO SERVICE.

## CEILING & LIGHTING LEGEND

2' X 2' DROP CEILING WITH WHITE SPLINES.  
OPTIONAL PAINTED CEILING TILE AND SPLINE COLORS (SPLINES MUST BE PAINTED THE SAME COLOR AS TILES):  
BLONDE PAINT (SHERWIN WILLIAMS #SW 6128) \*CUSTOMER AREA ONLY\*  
WHEAT GRASS PAINT (SHERWIN WILLIAMS #SW 6408) \*CUSTOMER AREA ONLY\*

SYMBOL	DESCRIPTION	MANUF.	SUPPLY	ORDERED FROM	NO.	NOTES
	2'X2' RECESSED FLUORESCENT FIXTURE	LIGHTOLIER	SPECIALTY STORE LIGHTING	DAI	9	RECESSED FLUORESCENT FIXTURE (SP26GVA8F120S8). USES (2) PL-L40W/35/RS BIAX GGL LIGHT BULBS.
	2'X2' RECESSED FLUORESCENT FIXTURE W/PARABOLIC LENS	LIGHTOLIER	SPECIALTY STORE LIGHTING	DAI	7	RECESSED FLUORESCENT FIXTURE W/PARABOLIC LENS (CPA2G9LS2F120S8). USES (2) PL-L40W/35/RS BIAX GGL LIGHT BULBS.
	DOWNLIGHT (SERVICE AREA)	LIGHTOLIER	SPECIALTY STORE LIGHTING	DAI	4	RECESSED FIXTURE (1102P1/1146). USES (1) 45WPAR BULB
	VINYL DROP-IN		G.C.	G.C.	4	2' X 2' DROP-IN PANEL
	ACoustical DROP-IN		G.C.	G.C.	4	2' X 2' DROP-IN PANEL
	2' X 2' SURFACE MOUNTED LIGHT FIXTURE WITH SEPARATE EXHAUST FAN		G.C.	G.C.	1	STANDARD SURFACE MOUNTED FIXTURE WITH ENERGY SAVING BALLAST AND 40 WATT COIL WHITE TUBES. SEPARATE EXHAUST FAN WITH A 100 CFM AIR EXCHANGE REQUIRED.
	AMBER PENDANT LIGHT (LARGE)	TRUE TO FORM	SPECIALTY STORE LIGHTING	DAI	7	LARGE SUSPENDED PENDANT FIXTURE (SV/AST/10-PL). USES (1) 15W FLUO. LAMP (MAXLITE MLS15EA). PENDANT LIGHTS ARE PLACED AROUND THE PERIMETER OF THE RESTAURANT AND SHOULD BE INSTALLED AT A HEIGHT OF 6'-6" (98.1cm) FROM THE FLOOR TO THE BOTTOM OF THE FIXTURE. (A PENDANT STEM KIT IS AVAILABLE THROUGH SPECIALTY STORE LIGHTING FOR USE WITH HIGH CEILING). RECOMMEND INSTALLING CUSTOMER SEATING BEFORE PENDANT LIGHTS TO ALLOW FOR PRECISE PLACEMENT OF FIXTURES OVER TABLE TOPS.
	CEILING FAN	VILLA LIGHTING	DAI	DAI	3	MX2-AS/52CR REGENCY MX-EXCEL WITH 5 CHERRY FINISH BLADES. CAN BE INSTALLED AS DROP STYLE (WITH 6" OR 2" STEM) OR HUGGER (FLUSH) STYLE.

PRINTED: 11/8/2010

REVISION: BY DATE

STORE MUST BE CONSTRUCTED AS DESIGNED IN THESE FLOOR PLANS SUBJECT TO FEDERAL, STATE AND LOCAL LAWS. RECIPIENT IS RESPONSIBLE FOR ENSURING COMPLIANCE WITH ALL LAWS. IF MODIFICATIONS ARE NECESSARY, PLEASE CONTACT DAI'S STORE DESIGN DEPARTMENT FOR WRITTEN APPROVAL OF THE REQUIRED CHANGES.

THIS DRAWING IS FURNISHED BY DOCTORS ASSOCIATES INC. (DAI) DBA SUBWAY. RECIPIENT MUST DETERMINE IF THIS DRAWING MUST BE SUBMITTED TO A LICENSED ARCHITECT OR SIMILAR PROFESSIONAL UNDER FEDERAL, STATE OR LOCAL LAW. ANY CHANGES MUST BE APPROVED BY DAI.

DO NOT SCALE DRAWING. WRITTEN DIMENSIONS TAKE PRECEDENCE OVER SCALED DIMENSIONS AND SHALL BE VERIFIED IN THE FIELD BY THE GENERAL CONTRACTOR AND/OR FRANCHISEE/OWNER. ANY DISCREPANCY IN DIMENSIONS SHALL BE BROUGHT TO THE IMMEDIATE ATTENTION OF DAI'S AREA DEVELOPMENT AGENT OR DESIGNATED FIELD REPRESENTATIVE.

THE GENERAL CONTRACTOR AND EACH SUB-CONTRACTOR SHALL MAKE HIS OWN INSPECTIONS AND MEASUREMENTS ON AND SUBWAY SHALL NOT BE HELD RESPONSIBLE FOR THE ACCURACY OF DIMENSIONS AND FOR ERRORS AND OMISSIONS IN THE DRAWINGS IF WRITTEN CONFIRMATION HAS NOT BEEN RECEIVED BY DAI'S STORE DESIGN DEPARTMENT.

THIS DRAWING AND THE INFORMATIONAL CONTENT HEREOF IS THE CONFIDENTIAL PROPERTY OF DAI AND IS PROVIDED SOLELY FOR THE USE OF AUTHORIZED FRANCHISEES. THEIR AGENTS AND CONTRACTORS. RECIPIENT AGREES NOT TO REPRODUCE, COPY, USE OR TRANSMIT THIS DRAWING AND/OR ITS INFORMATIONAL CONTENT IN WHOLE OR IN PART, OR TO ALLOW SUCH ACTION BY OTHERS, FOR ANY PURPOSE, EXCEPT WITH THE WRITTEN PERMISSION OF DAI. ACTING FOR SUBWAY. RECIPIENT FURTHER AGREES TO SUBMIT THIS DRAWING AND ANY PERMITTED COPIES HEREOF UPON DEMAND.

**SUBWAY**  
WORLD HEADQUARTERS  
(203) 877-4281  
(800) 888-4848  
325 BIG DRIVE  
MILFORD, CT 06461

LOCATION:  
STORE # 50755  
2411E. VALLEY PKWAY.  
ESCONDIDO, CA

FRANCHISEE:  
MARWAHA

DEVELOPMENT AGENT:  
MARWAHA

DATE:  
SEPT. 23, 2010

DESIGNED BY:  
RUSSELL RUMFORD

DRAWN BY:  
R.S.R.

REVIEWED BY:

SCALE: 1/4" = 1'-0"

SHEET #:  
1 OF 2